



## BID PROPOSAL

Please return to: Westside Housing Organization  
919 W 24<sup>th</sup> Street  
Kansas City, MO 64108

Pre-bid Date: Monday January 28<sup>th</sup> at 1:20 pm

Property Address: 129 Spruce

Owner Name: Consuelo Rivera

Phone: 816-216-1407 DO NOT CONTACT CLIENT PRIOR TO PREBID

**Bid Due Date: Tuesday, February 12th, 2019 by 10:00 AM**

For consideration stated below, the undersigned proposed to furnish all labor and materials necessary to complete the work as described in the attached itemized scope of work for the property listed above.

**Total Bid:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Signature:** \_\_\_\_\_

**Company Name:** \_\_\_\_\_

**Company Address:** \_\_\_\_\_

**Company Phone:** \_\_\_\_\_

# SPECS BY LOCATION/TRADE

12/17/2018

Pre-Bid Site Visit: \_\_\_\_\_  
 Bidding Open Date: \_\_\_\_\_  
 Bidding Close Date: \_\_\_\_\_  
 Initial: \_\_\_\_\_

Case Number: \_\_\_\_\_  
 Project Manager: \_\_\_\_\_  
 Phone: \_\_\_\_\_

Address: 129 Spruce

Unit: Unit 01

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
<b>Trade: 1 General Requirements</b>					
10	<p><b>OWNER ACCEPTS SCOPE OF WORK</b></p> <p>The undersigned applicant(s) certifies that he/she has participated in the development of this Work Scope with the "Date inspected" date of _____ &amp; referred to as Exhibit 1. After careful review the applicant understands &amp; accepts the work described &amp; has initialed &amp; dated each page of this Work Scope.</p> <p>X _____ Date X _____ DATE                      Applicant Date Applicant DATE</p>	1.00	DU	_____	_____
14	<p><b>CONTRACTOR ACCEPTS SCOPE OF WORK</b></p> <p>The undersigned contractor certifies that he/she has carefully reviewed &amp; agrees to perform the work described in this Work Scope with the "Date Inspected" date of _____ &amp; referred to as Exhibit 1. The contractor shall initial &amp; date each item of the Work Scope.</p> <p>X _____ Date _____                      Contractor Date</p>	1.00	DU	_____	_____
31	<p><b>CONSTRUCTION DEFINITIONS</b></p> <p>"Install" means to purchase, set up, test and warrant a new component. "Replace" means to remove and dispose of original material, purchase new material, deliver, install, test and warrant. "Repair" means to return a building component to like new condition through replacement, adjustment and recoating of parts. "Reinstall" means to remove, clean, store and install a component. Please initial this after reading.</p>	1.00	GR	_____	_____
35	<p><b>VERIFY QUANTITIES/MEASUREMENTS</b></p> <p>All measurements are for the contractor's convenience prior to a mandatory site inspection to verify all dimensions. No claim for additional funds due to discrepancies in measurements or quantities shall be honored if not submitted at the time of the initial proposal. During the contractor's walk through we will make an effort to verify all measurements so that all contractors will be bidding on the same quantities. IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL MEASUREMENTS. Please initial after reading.</p>	1.00	GR	_____	_____
37	<p><b>ELECTRICAL PERMIT REQUIRED</b></p> <p>Prior to the start of work, the contractor shall create any documentation necessary to apply for, pay for and receive an electrical permit on behalf of the owner. It will be the contractors responsibility to order an inspection and meet with the inspector or designate somebody to meet with the inspector. The contractor shall provide a copy of the "passed" electrical inspection on all work requiring an electrical permit.</p>	1.00	EA	_____	_____

Address: 129 Spruce

Unit: Unit 01

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 1	General Requirements				
45	<b>CONTRACTOR PRE-BID SITE VISIT</b> The contractor must attend the required prebid inspection the property. Submission of a bid is presumptive evidence that the bidder has thoroughly examined the site and is conversant with the requirements of the local jurisdiction. Contractor must sign in at each property inspection. Unless otherwise noted, bids are due at our office by 11:00 a.m. one week after the contractor's walk through. The contractor must submit bids in a sealed envelope prior to bid opening date and time. If more than one bid opens at the same day and time you may insert all bids for this date and time in the same sealed envelope. Please initial after reading.	1.00	DU	_____	_____
55	<b>WORK TIMES</b> Contractors and their Subcontractors shall schedule working times with homeowner and primarily be between 8:00am and 5:00pm Monday through Friday. Requests to work on weekends and before or after these hours must be approved by the homeowner. NOTE: WHO will do an inspection of all work and the contractor and Home Owner will sign all payment documents. Please initial after reading.	1.00	GR	_____	_____
77	<b>NEW MATERIALS REQUIRED</b> All materials used in connection with this work write-up are to be new, of first quality and without defects - unless stated otherwise or pre-approved by Owner and Construction Specialist. Please initial after reading.	1.00	GR	_____	_____
90	<b>1 YEAR GENERAL WARRANTY</b> Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Further, contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract prior to release of the final payment. Please initial after reading.	1.00	DU	_____	_____
120	<b>FINAL CLEAN</b> Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work areas.	1.00	EA	_____	_____

Location Total: \_\_\_\_\_

Location: 2 - Basement

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 23	Electric				
7475	<b>ELECTRIC SERVICE--200 AMP</b> Dispose of old electric service to code legal dump. Install a 200 amp, main disconnect, 110/220 volt, 24 circuit panel board, meter socket, weather head, service cable, and ground rod and cable. Caulk exterior service penetration. It is the electrical	1.00	EA	_____	_____

Address: 129 Spruce

Unit: Unit 01

Location: 2 - Basement

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec # Spec

Quantity Units Unit Price Total Price

Trade: 23 Electric

contractors responsibility to get meter spot from KCP&L. All work to be to city code requirements.

Location Total: \_\_\_\_\_

Location: 3 - Half Bath

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec # Spec

Quantity Units Unit Price Total Price

Trade: 22 Plumbing

7005 COMMODE--REFURBISH

1.00 EA \_\_\_\_\_

Install an anti-siphon fill valve. Replace flap valve and adjust water height to effect proper flushing action.

Location Total: \_\_\_\_\_

Unit Total for 129 Spruce , Unit Unit 01: \_\_\_\_\_

Address Grand Total for 129 Spruce : \_\_\_\_\_

Bidder: \_\_\_\_\_