



## BID PROPOSAL

Please return to: Westside Housing Organization  
919 W 24<sup>th</sup> Street  
Kansas City, MO 64108

Pre-bid Date: Monday January 28<sup>th</sup> at 2:15 pm

Property Address: 3815 Virginia

Owner Name: Joseph Alaniz

Phone: 816-531-3752 DO NOT CONTACT CLIENT PRIOR TO PREBID

**Bid Due Date: Tuesday, February 12th, 2019 by 10:00 AM**

For consideration stated below, the undersigned proposed to furnish all labor and materials necessary to complete the work as described in the attached itemized scope of work for the property listed above.

**Total Bid:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Signature:** \_\_\_\_\_

**Company Name:** \_\_\_\_\_

**Company Address:** \_\_\_\_\_

**Company Phone:** \_\_\_\_\_

# SPECS BY LOCATION/TRADE

12/12/2018

Pre-Bid Site Visit: \_\_\_\_\_  
 Bidding Open Date: \_\_\_\_\_  
 Bidding Close Date: \_\_\_\_\_  
 Initial: \_\_\_\_\_

Case Number: \_\_\_\_\_  
 Project Manager: \_\_\_\_\_  
 Phone: \_\_\_\_\_

**Address: 3815 Virginia** **Unit: Unit 01**

**Location: 1 - General Requirements** Approx. Wall SF: 0      Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
<b>Trade: 1</b>	<b>General Requirements</b>				
10	<b>OWNER ACCEPTS SCOPE OF WORK</b> The undersigned applicant(s) certifies that he/she has participated in the development of this Work Scope with the "Date inspected" date of _____ & referred to as Exhibit 1. After careful review the applicant understands & accepts the work described & has initialed & dated each page of this Work Scope. X _____ X _____ Applicant      Date      Applicant      DATE	1.00	DU	_____	_____
14	<b>CONTRACTOR ACCEPTS SCOPE OF WORK</b> The undersigned contractor certifies that he/she has carefully reviewed & agrees to perform the work described in this Work Scope with the "Date Inspected" date of _____ & referred to as Exhibit 1. The contractor shall initial & date each item of the Work Scope. X _____ Contractor      Date	1.00	DU	_____	_____
31	<b>CONSTRUCTION DEFINITIONS</b> "Install" means to purchase, set up, test and warrant a new component. " Replace" means to remove and dispose of original material, purchase new material, deliver, install, test and warrant. "Repair" means to return a building component to like new condition through replacement, adjustment and recoating of parts. "Reinstall" means to remove, clean, store and install a component. Please initial this after reading.	1.00	GR	_____	_____
35	<b>VERIFY QUANTITIES/MEASUREMENTS</b> All measurements are for the contractor's convenience prior to a mandatory site inspection to verify all dimensions. No claim for additional funds due to discrepancies in measurements or quantities shall be honored if not submitted at the time of the initial proposal. During the contractor's walk through we will make an effort to verify all measurements so that all contractors will be bidding on the same quantities. IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL MEASUREMENTS. Please initial after reading.	1.00	GR	_____	_____
45	<b>CONTRACTOR PRE-BID SITE VISIT</b> The contractor must attend the required prebid inspection the property. Submission of a bid is presumptive evidence that the bidder has thoroughly examined the site and is conversant with the requirements of the local jurisdiction. Contractor must sign in at each property inspection. Unless otherwise noted, bids are due at our office by 11:00 a.m. one week after the contractor's walk through. The contractor must submit bids in a sealed	1.00	DU	_____	_____

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 1	<b>General Requirements</b>				
	envelope prior to bid opening date and time. If more than one bid opens at the same day and time you may insert all bids for this date and time in the same sealed envelope. Please initial after reading.				
55	<b>WORK TIMES</b> Contractors and their Subcontractors shall schedule working times with homeowner and primarily be between 8:00am and 5:00pm Monday through Friday. Requests to work on weekends and before or after these hours must be approved by the homeowner. NOTE: WHO will do an inspection of all work and the contractor and Home Owner will sign all payment documents. Please initial after reading.	1.00	GR	_____	_____
77	<b>NEW MATERIALS REQUIRED</b> All materials used in connection with this work write-up are to be new, of first quality and without defects - unless stated otherwise or pre-approved by Owner and Construction Specialist. Please initial after reading.	1.00	GR	_____	_____
90	<b>1 YEAR GENERAL WARRANTY</b> Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Further, contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract prior to release of the final payment. Please initial after reading.	1.00	DU	_____	_____
120	<b>FINAL CLEAN</b> Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work area.	1.00	EA	_____	_____

Location Total: \_\_\_\_\_

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 7	<b>Masonry</b>				
1232	<b>STONE-REPOINT</b> Rebuild deteriorated stone wall at north end of front porch to match existing as closely as possible, using existing salvageable stones and purchasing new as needed to complete the wall to match existing as closely as possible. Install new concrete cap at top of this rebuilt wall to match remaining stone walls around existing porch. Match color, design and texture of existing mortar as closely as possible. Provide barricades and drop clothes.	132.00	SF	_____	_____
1290	<b>STONE ENDCAPS--REBUILD</b> Rebuild deteriorated stone wall at stone walls on each side of front porch steps to match existing as closely as possible, using existing salvageable stones and purchasing new as needed to	36.00	SF	_____	_____

Address: 3815 Virginia

Unit: Unit 01

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor-SF: 0

Spec # Spec

Quantity Units Unit Price Total Price

Trade: 7 Masonry

complete the wall to match existing as closely as possible.  
Reinstall existing stone caps on these walls. Match color,  
design and texture of existing mortar as closely as possible.  
Provide barricades and drop clothes.

Location Total: \_\_\_\_\_

Unit Total for 3815 Virginia , Unit Unit 01: \_\_\_\_\_

Address Grand Total for 3815 Virginia : \_\_\_\_\_

Bidder: \_\_\_\_\_